Testing of hotun tundishes to determine their maximum cold-water flow capacity



Prepared by: Kiwa Limited Prepared for: RA Tech UK Ltd

Report Number: 30913

Date: 10 August 2018

This report may only be published and forwarded to third parties in its complete, unabridged form. The publication or dissemination of extracts, summaries, appraisals or any other adaptation and alterations, in particular for advertising purposes, is only permissible with the prior written permission of Kiwa Limited

The test results presented in this report refer solely to the test object stated

Trust
Quality
Progress



Testing of hotun tundishes to determine their maximum cold-water flow capacity

Report number:	30913
Prepared for:	RA Tech UK Ltd
Date:	28 August 2018
Status:	Final
Prepared by:	
T R Dennish	Principal Consultant
Approved by:	
Iain Summerfield	Principal Consultant
Commercial in confidence	

Kiwa Ltd Kiwa House Malvern View Business Park Bishops Cleeve Cheltenham GL52 7DQ

Tel: +44 (0)1242 677877 Fax: +44 (0)1242 676506 E-mail: enquiries@kiwa.co.uk Web: www.kiwa.co.uk

30913 / RA Tech UK Ltd © Kiwa Ltd 2018



Executive Summary

A range of tundishes of novel design called 'hotun' were supplied by RA Tech UK Ltd. These have been tested to determine their maximum cold-water flow capacity in two different configurations.

The following results were obtained:

			Average Maximur	n flow (L/min)
			Configur	ation
Product	Inlet	Outlet	1	2
hotun sf	15 mm	22 mm	22.3	12.8
hotun hiflo sf	15 mm	32 mm	45.1	35.2
hotun xlsf	22 mm	32 mm	54.3	38.1

Where configuration 1 is with 300mm vertical pipe at outlet

And configuration 2 is with 90° elbow at outlet

30913 / RA Tech UK Ltd © Kiwa Ltd 2018



Table of contents

1	Intro	oduction	. 3
2	Tes	sting program	. 3
		sults	
		Results Details	
		Results Summary	



1 Introduction

RA Tech UK Ltd have requested the maximum cold-water flow capacity of their range of hotun tundishes be determined. Kiwa received three tundishes for testing and have tested each of these in two configurations. This report documents this testing and results

2 Testing program


Three products were supplied for testing:

- hotun sf 15 mm inlet 22 mm outlet
- hotun hiflo sf 15 mm inlet 32 mm outlet
- hotun xlsf 22 mm inlet 32 mm outlet

These are tundishes with an automatic closing device on the outlet to prevent odours etc coming back up the discharge pipe.

Each product was to be tested in two configurations:

- 1. Testing with minimum 200 mm straight pipe on inlet and 300 mm vertical discharge to then elbow into nominal 200 mm horizontal into soil stack
- 2. Testing with minimum 200 mm straight pipe on inlet and close coupled elbow into discharge via nominal 200 mm horizontal into soil stack






Test Method

Each product was tested in each configuration at least two times, with notes and photographs taken of the water flow/level in the tundish.

The test rig is shown below. Cold water was circulated around the rig at a rate controlled using a hand valve and monitored on an accurate flowmeter.



Each test was started at low flow and it was ensured that the lip and structs of the tundish were dry. The water pump was switched on with water flow set at zero or low flow and the flow was slowly increased stopping occasionally to photograph the state of the flow in the tundish. Notes were taken on the state of water in the tundish and any splashing or overflow occurring.



3 Results

3.1 Results Details

Test	1
Configuration	1
Date	6/8/2018 11:40
Unit under test	hotun hiflo sf
Max flow before overflow (L/min)	39.9

Test	2
Configuration	1
Date	6/8/2018 12:07
Unit under test	hotun hiflo sf
Max flow before overflow (L/min)	45.0

Test	3
Configuration	1
Date	6/8/2018 15:11
Unit under test	hotun hiflo sf
Max flow before overflow (L/min)	45.2



Test	4
Configuration	1
Date	6/8/2018 15:43
Unit under test	hotun sf
Max flow before overflow (L/min)	22.5

Test	5
Configuration	1
Date	6/8/2018 16:14
Unit under test	hotun sf
Max flow before overflow (L/min)	22.2

Test	6
Configuration	1
Date	6/8/2018 15:43
Unit under test	hotun sf
Max flow before overflow (L/min)	22.2



Test	7
Configuration	1
Date	7/8/2018 15:44
Unit under test	hotun xlsf
Max flow before overflow (L/min)	54.2 (occasional small dribbles from >50 L/min)

Test	8
Configuration	1
Date	7/8/2018 16:07
Unit under test	hotun xlsf
Max flow before overflow (L/min)	54.4 (occasional small dribbles from >50
	L/min)



Test	9
Configuration	2
Date	8/8/2018 13:55
Unit under test	hotun xlsf
Max flow before overflow (L/min)	38.0

Test	10
Configuration	2
Date	8/8/2018 14:08
Unit under test	hotun xlsf
Max flow before overflow (L/min)	38.1



Test	11
Configuration	2
Date	8/8/2018 14:31
Unit under test	hotun hiflo sf
Max flow before overflow (L/min)	34.8

Test	12
Configuration	2
Date	8/8/2018 14:46
Unit under test	hotun hiflo sf
Max flow before overflow (L/min)	35.5



Test	13
Configuration	2
Date	8/8/2018 14:31
Unit under test	hotun sf
Max flow before overflow (L/min)	12.5

Test	14
Configuration	2
Date	8/8/2018 15:48
Unit under test	hotun sf
Max flow before overflow (L/min)	13.5

Test	15
Configuration	2
Date	8/8/2018 16:01
Unit under test	hotun sf
Max flow before overflow (L/min)	12.5



3.2 Results Summary

		Average Maximum flow (L/min)		
		Configuration		
Product	Inlet	Outlet	1	2
hotun sf	15 mm	22 mm	22.3	12.8
hotun hiflo sf	15 mm	32 mm	45.1	35.2
hotun xlsf	22 mm	32 mm	54.3	38.1

Where configuration 1 is with 300mm vertical pipe at outlet And configuration 2 is with 90° elbow at outlet

